BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineer
Yelahanka Division
B.B.M.P. Bengaluru - 64
No:EE/YNK-D/E-PMT/01/2013-14 Dated: 01-06-2013

APPROVED TENDER SCHEDULE –'B'

Item No: 5

Name of Work: -Providing Asphalting to Desthara hheedhi main road in ward No-02 of yelahanka Sub Division.

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri.H S Nataraj	
				Rate	Rate in Words
1	KSRB 2-2.1 ; earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, slacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications, specification, with all lead and lift etc comptete as per specification and direction of engineer incharge of the work.	Cum	152.25	140.00	Rupees one hundred forty only
2	KSRB 100-1 Loading and unloading ofstone aggregates / sand/ kanker/ Moorum /soil KSRRB M100-1 Placing tipper at loading with front end loader dumpting turning for return trip excluding time for haulged and return trip complete as per specification item No 17.1 page 141 and KSRB M.100.4.1 costof haulage excluding loading and unloading MORTH to a distance with all lead and lift etc complete as per specification and direction of engineer incharge of the work.	Cum	152.25	70.00	Rupees seventy only
3	KSRRB M400-17. Providing, laying spreading and compacting graded stones aggregate to wet mix macadam specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying, in uniform layers with paver in sub base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH specification with all lead and lift etc complete as per specification and direction of engineer incharge of the work.	Cum	131.25	1100.00	Rupees one thousand one hundred only
4	KSRRB 500-2. Cleaning the existing black topped surface with brooms, soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries complete as per specifications. MORTH chapter 5 with all lead and lift etc complete as per specification and direction of engineer incharge of the work.	Sqm	1575.00	2.00	Rupees [illegible] only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri.H S Nataraj	
				Rate	Rate in Words
5	KSRRB M500-6: providing and applying primer coat with bitumen emulsion on prepared surface of granular base including clearing of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per specifications. MORTH specification with all lead and lift etc complete as per specification and direction of engineer incharge of the work.	Sqm	1375.00	44.00	Rupees forty four only
6	KSRRD M500-16: Providing and laying semi dense bituminous concrete 25mm thick with 100-120 TPH batch type HMP producing and average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 4.5 to 5% of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 500.8 complete in all respects as per specifications with all lead and lift etc complete as per specification and direction of engineer incharge of the work.	Cum	34.38	8500.00	Rupees eight thousand eight hundred only
7	KSRB-4-1.3 : Providing and laying in position plain cement concrete of mix M7.5 withOPC cement at 160kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification with all lead and lift etc complete as per specification and direction of engineer incharge of the work.	Cum	10.80	4200.00	Rupees four thousand two hundred only
8	KSRB 4.2.2 : Providing and laying in position plain cement concrete of mix M20 withOPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.87cum and fine aggregates @0.455cum with superplastesisre @ 3lts conforming to IS9103-1999Reffirmed machine mixed exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls(any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour HOM of machinery, curing, complete as per specifications. Specification, with all lead and lift etc complete as per specification and direction of engineer incharge of the work.	Cum	32.40	5300.00	Rupees five thousand three hundred only
9	KSRB 4.9.2 providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification with all lead and lift etc complete as per specification and direction of engineer incharge of the work.	Quintal	22.68	7600.00	Rupees seven thousand six hundred only

Print Count : 2

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri.H S Nataraj	
				Rate	Rate in Words
10	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, attached pilasters,biltresses,buttresses plinth and string course including cost of all materials, labour complete as per specifications. Specification with all lead and lift etc complete as per specification and direction of engineer incharge of the work.	Sqm	288.00	255.00	Rupees two hundred fifty five only
11	RCC Precast covering slab for drain (10cm thick) with all lead and lift etc complete as per specification and direction of engineer incharge of the work.	Sqm	31.50	1240.00	Rupees one thousand two hundred forty only

Signature of the Contractor

5/9/13

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64